

# Takeoff Record

Name	Area	Length	Count
<b>Roof A</b>			
Flat Roof	76691.999	1114'8"	9
Gravel Stop		518'0"	
3'6" ' Coping	2546.788	596'8"	
Roof Hatch	16.50	11'0"	1
Curb/Curb Exp Joint	982.922	245'9"	
Curb	252.00	168'0"	7
Curb (HVAC)	192.00	128'0"	4
Skylight	288.00	192'0"	6
Plumbing Stack			6
Pitch Pan			9
Drain (Existing)			12
Gas Line		494'11"	
Satelite dish			1
Ponding	2862.073		
<b>Roof B</b>			
Flat Roof	15525.00	780'0"	6
Gravel Stop		480'0"	
18" Base Flashing	450.00	300'0"	
Curb	216.00	144'0"	6
Roof Hatch	16.50	11'0"	1
Curb (HVAC)	96.00	64'0"	2
Plumbing Stack			2
Pitch Pan			8
Drain (Existing)			6
Gas Line		171'3"	
Ladder			1